

Please read and understand the complete instructions prior to assembly and use of your outdoor leisure product. Customer agrees not to hold Dundalk LeisureCraft Inc. and any of its authorized dealers liable for improper installation, maintenance and repair of this product



Requirements:

- * 2 People (recommended)
 - * Carpenter's Hammer
- * Cordless Drill (we supply the bit)
 - * Tape Measure
 - * Rubber Mallet

View the assembly process on You Tibe





Organize your pieces neatly on the ground.



Set up the side wall pieces as shown.



Slide the front wall into place.



Holding the walls flush together, secure them using the provided 2 ½" (64mm) screws from the inside of the front wall into the side walls.





With a helper, place the bar top on top of the assembled frame.



Secure the front and side walls to the bar top from underneath.

Be careful not to overtighten as screws will go through top of bar.



To assemble the cabinet in your southern fantasy tiki bar it is important to use the top and bottom shelves in the correct location.

To tell the difference between the top and bottom, determine the pre drilled kreg hole location.

Bottom- Holes facing ends Fig.1



The top shelf will have the pre drilled holes facing the edges only. Fig. 2

3





Place the bottom Shelf on the ground with the pre drilled holes on the bottom.

With the doors opening outward, line up the cabinet so it is flush to the edge of the bottom shelf and secure with 2 1/2" (64mm) screws.



Ensure the top shelf is flush to the edge of the shelf cabinet and secure from underneath up into the top shelf with 2 ½" (64mm) screws.

The pre drilled holes in the top shelf should be facing away from the cabinet and on the bottom.



Lay the tiki bar on its front.

(use a blanket to prevent it from getting damaged)

Gently place the completed cabinet inside the tiki bar. Note the orientation of the door handles should be to the top.



Make sure the bottom of the assembled cabinet is flush to the bottom of the tiki bar and secure with 2 $\frac{1}{2}$ " (64mm) screws in the pre drilled Kreg holes.





Stand the tiki bar back up.



Secure the top shelf to the front wall using 2 ½" (64mm) screws in the pre drilled Kreg holes.



Slide your bar posts into the holes in the bar top.



Finesse the bar posts in until they hit the bottom.





Lay out your roof beams.



Insert the roof supports into the holes in the roof beams.



Insert the roof beam onto the other side of the roof supports. Tap tight with a rubber mallet.



Make sure the roof supports are straight and secure each joint with a 2 $\frac{1}{2}$ " (64mm) screw.





Locate the top roof staves.

These will have a 45 degree cut on the top side.



With the roof staves overhanging on each end of the assembled roof evenly, hold the roof staves flush together at the top of the roof and secure to each roof support with a 2" (51mm) screw.



Install the remaining roof staves working your way down the roof.

Put 2 - 2" (51mm) screws into the stave at each roof support



The remaining roof staves will have a tongue and groove pattern and may need to be tapped with a rubber mallet to ensure they are tight together to each other before screwing.





The staves for the bottom of each side will not have the dado cut in them.



Unroll your palm thatch and line it up with the top of ones side of the roof.



Using a hammer, fasten the palm thatch to the roof using the provided staple clips.



These should be placed approximately every 8" and at least three rows per side.

Repeat on other side of roof.





With at least 2 people, lift the assembled roof onto the top of the bar posts.



Using a tape measure, ensure the overhang on each end of the roof sits even.



Once the roof is centered pre drill holes in the roof beam.



Secure each corner of the roof beam to the assembled roof using the provided 3 ½" (89mm) screws.





Secure the assembled bar to the bar posts from the inside using a 2 ½" (64mm) screw.

Repeat on other end of bar.

Congratulations on the assembly of your new Southern Fantasy Tiki Bar!



- * The Southern Fantasy Tiki Bar is coated with a water based outdoor clear coat. To maintain this look you may have to re apply the clear coat after 2 or 3 years if the tiki bar is left outside all year.
- * The natural palm thatch roofing material should be removed and stored indoors in the winter or when not in use for an extended period of time. Simply covering with a tarp for the winter is not advised as it could cause the natural thatch to mold.
 - * The synthetic thatch can stay outside year round.

For assistance in the assembly of your Tiki Bar please visit our support page at: https://www.dundalkleisurecraft.com/support/

> Or to view the assembly process got to: https://www.youtube.com/watch?v=WirE7acu1Fc&t=9s